1512 S BATAVIA AVENUE GENEVA, IL 60134

630-232-0104

An MALION Technical Center

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

FOR: **Turf Design** Elgin, IL

CONDUCTED: 2018-09-28 ON: Pyramid ceiling tiles

TEST METHOD

Riverbank Acoustical LaboratoriesTM is accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) as an ISO 17025:2005 Laboratory (NVLAP Lab Code: 100227-0) and for this test procedure. The test reported in this document conformed explicitly with ASTM C423-17: "Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method." The specimen mounting was performed according to ASTM E795-16: "Standard Practices for Mounting Test Specimens During Sound Absorption Tests." A description of the measuring procedure and room qualifications is available upon request.

DESCRIPTION OF THE SPECIMEN

The test specimen was designated by the manufacturer as Pyramid ceiling tiles. A full external visual inspection performed on the test specimen by Riverbank personnel verified the manufacturer's description.

Panel

Trade Name:	Pyramid
Material ID:	03862
Materials:	Formed polyethylene terephthalate felt
Dimensions:	16 @ 609.6 mm (24 in.) x 609.6 mm (24 in.)
Wall Thickness:	5 mm (0.197 in.)
Overall Thickness:	Minimum @ 50.29 mm (1.98 in.)
	Maximum @ 196.85 mm (7.75 in.)
Overall Weight:	10.77 kg (23.75 lbs)
Installation:	Arranged such that divot feature on all tiles is oriented toward
	south wall of test chamber
Physical Measures	
Size:	2.44 m (96.0 in) wide by 2.44 m (96.0 in) long

DILC.	2.11 m (90.0 m) where 09 2.11 m (90.0
Thickness:	0.2 m (7.75 in)
Weight:	10.77 kg (23.75 lbs)
Mass per Unit Area:	1.81 kg/m ² (0.37 lbs/ft ²)
Calculation Area:	5.946 m ² (64 ft ²)

Test Environment

Room Volume:	291.98 m ³
Temperature:	20.9 °C \pm 0.0 °C (Requirement: \geq 10 °C and \leq 5 °C change)
Relative Humidity:	$67.35 \% \pm 0.1 \%$ (Requirement: $\ge 40 \%$ and $\le 5 \%$ change)
Barometric Pressure:	99.1 kPa (Requirement not defined)
® RIVERBANK AC	COUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES I WITH ISO/IEC 17025-2005 AND FOR THIS PROCEDIIRE THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAI
$2 / \lambda \rangle (\cap)$ ACCORDANCE	WITH ISO/IEC 17025-2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLA

 RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

WALLACE CLEMENT SA Sound Absorption RALTM-A18-323

Page 1 of 7

Test Report

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RAL[™]-A18-323 Page 2 of 7

Turf Design 2018-09-28



Figure 1 - Specimen mounted in test chamber



Figure 2 – Detail of individual tile



RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

An MALION Technical Center

1512 S BATAVIA AVENUE GENEVA. IL 60134 630-232-0104

Turf Design

2018-09-28

MOUNTING METHOD

Type E-400 Mounting: The test specimen was mounted with an airspace behind it. The number designates the distance in mm from the exposed face of the test specimen to the test surface, rounded to the nearest integer multiple of 5. For the purposes of this report, the mounting designation uses the point on the specimen face where minimum overall thickness was measured for reference. Perimeter edges were sealed with metal framing.

TEST RESULTS

1/3 Octave Center			
Frequency	Total Absorption	Total Absorption	Absorption
(Hz)	(m ²)	(Sabins)	Coefficient
100	5.21	56.08	0.88
** 125	6.98	75.09	1.17
160	4.57	49.20	0.77
200	5.44	58.57	0.92
** 250	5.83	62.79	0.98
315	5.21	56.12	0.88
400	4.83	51.97	0.81
** 500	5.10	54.86	0.86
630	5.52	59.43	0.93
800	5.52	59.47	0.93
** 1000	5.63	60.62	0.95
1250	5.58	60.06	0.94
1600	5.76	61.96	0.97
** 2000	5.86	63.08	0.99
2500	5.70	61.36	0.96
3150	5.80	62.43	0.98
** 4000	6.04	65.00	1.02
5000	6.23	67.05	1.05

SAA = 0.93NRC = 0.95



RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

RIVERBANK.ALIONSCIENCE.COM

Test Report

WALLACE CLEMENT SABINE

FOUNDED 1918 BY

RALTM-A18-323 Page 3 of 7

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

RALTM-A18-323

Test Report

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Page 4 of 7

Turf Design

2018-09-28

TEST RESULTS (Continued)

The sound absorption average (SAA) is defined in ASTM C423-17 Section 3.1.1 as the average, rounded to the nearest integer multiple of 0.01, of the sound absorption coefficients of a material for the twelve one-third octave bands from 200 Hz through 2500 Hz, inclusive.

The noise reduction coefficient (NRC) is defined from previous versions of ASTM C423 as the average of the sound absorption coefficients at 250 Hz, 500 Hz, 1000 Hz, and 2000 Hz, expressed to the nearest integer multiple of 0.05.

Tested by Marc Sciaky

Marc Sciaky Experimentalist

Report by Malcolm

Acoustician

Approved b Eric P. Wolfram Laboratory Manager



INVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

Turf Design

2018-09-28

An MALION Technical Center


RIVERBANK.ALIONSCIENCE.COM

Test Report

FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-A18-323

Page 5 of 7





RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

RALTM-A<u>18-323</u>

Page 6 of 7

Test Report

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Turf Design

2018-09-28

APPENDIX A: Extended Frequency Range Data

Specimen: Pyramid ceiling tiles (See Full Report)

The following non-accredited data were obtained in accordance with ASTM C423-17, but extend beyond the defined frequency range of 100Hz to 5,000Hz. These unofficial results are representative of the RAL test environment only and intended for research & comparison purposes.

1/3 Octave Band Center Frequency (Hz)	Total Absorption (Sabins)	Absorption Coefficient
31.5	14.68	0.23
40	14.62	0.23
50	26.48	0.41
63	41.23	0.64
80	29.88	0.47
100	56.08	0.88
125	75.09	1.17
160	49.20	0.77
200	58.57	0.92
250	62.79	0.98
315	56.12	0.88
400	51.97	0.81
500	54.86	0.86
630	59.43	0.93
800	59.47	0.93
1000	60.62	0.95
1250	60.06	0.94
1600	61.96	0.97
2000	63.08	0.99
2500	61.36	0.96
3150	62.43	0.98
4000	65.00	1.02
5000	67.05	1.05
6300	66.04	1.03
8000	70.74	1.11
10000	70.80	1.11
12500	70.77	1.11



RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An MALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

RALTM-A18-323

Test Report

FOUNDED 1918 BY WALLACE CLEMENT SABINE

Page 7 of 7

Turf Design

2018-09-28

APPENDIX B: Instruments of Traceability

Specimen: Pyramid ceiling tiles (See Full Report)

		Serial	Date of	Calibration
Description	Model	<u>Number</u>	Certification	Due
System 1	Type 3160-A-4/2	3160- 106968	2018-08-09	2019-08-09
Bruel & Kjaer Mic And Preamp C	Type 4943-B-001	2311439	2018-03-27	2019-03-27
Bruel & Kjaer Pistonphone	Type 4228	2781248	2018-08-06	2019-08-06
Omega Digital Temp., Humid. And Pressure Recorder	OM-CP- PRHTemp2000	P97844	2018-02-03	2019-02-03

END



INVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2005 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT. THIS REPORT SHALL NOT BE MODIFIED WITHOUT THE WRITTEN APPROVAL OF RAL. THE RESULTS REPORTED APPLY ONLY TO THE SPECIFIC SAMPLE SUBMITTED FOR TESTING; RAL ASSUMES NO RESPONSIBILITY FOR THE PERFORMANCE OF ANY OTHER SAMPLE.