

Test Report

SPONSOR: **Turf Design**
Elgin, IL

Sound Absorption
RAL™-A19-046

CONDUCTED: 2019-02-05

Page 1 of 8

ON: Switchblade C2 over fissured ceiling tiles

TEST METHODOLOGY

Riverbank Acoustical Laboratories™ is accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) as an ISO 17025:2005 Laboratory (NVLAP Lab Code: 100227-0) and for this test procedure. The test reported in this document conformed explicitly with ASTM C423-17: "Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method." The specimen mounting was performed according to ASTM E795-16: "Standard Practices for Mounting Test Specimens During Sound Absorption Tests." A description of the measurement procedure and room specifications are available upon request. The results presented in this report apply to the sample as received from the test sponsor.

INFORMATION PROVIDED BY SPONSOR

The test specimen was designated by the sponsor as Switchblade C2 over fissured ceiling tiles. The following nominal product information was provided by the sponsor prior to testing. The accuracy of such sponsor-provided information can affect the validity of the test results.

Product Under Test

Trade Name: Switchblade
Material ID: C2
Manufacturer: Turf Design

SPECIMEN MEASUREMENTS & TEST CONDITIONS

Through a full external visual inspection performed on the test specimen, Riverbank personnel verified the following information:

Test Specimen (in order of installation)

Layer 1

Materials: Fissured ceiling tile, wet-formed mineral fiber substrate
Dimensions: 8 @ 1212.85 mm (47.75 in.) x 603.25 mm (23.75 in.)
2 @ 1212.85 mm (47.75 in.) x 330.2 mm (13 in.)
Thickness: 14.27 mm (0.562 in.)
Overall Weight: 20.18 kg (44.5 lbs)

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An  ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report

Turf Design
2019-02-05

RAL™-A19-046
Page 2 of 8

Test Specimen (continued)

Layer 2

Material: Polyethylene terephthalate felt
Dimensions: 28 @ 598 mm (23.543 in.) x 152 mm (5.984 in.)
3 @ 295.27 mm (11.625 in.) x 152 mm (5.984 in.)
Thickness: Maximum @ 27 mm (1.063 in.)
Minimum @ 24.5 mm (0.965 in.)
Key Geometry: Center felt piece @ 9 mm (0.354 in.) thick @ 50 mm (1.969 in.) deep
9 mm (0.354 in.) thick felt pieces adhered to both sides of center piece
Three (3) pieces cut to fit mounting area dimensions
Installation: Mounted vertically in square grid pattern, thickest edge facing Layer 1
Overall Weight: 11.34 kg (25 lbs)

Overall Specimen Measurements

Size: 2.74 m (108.0 in) wide by 2.43 m (95.5 in) long
Thickness: 0.17 m (6.562 in)
Weight: 31.52 kg (69.5 lbs)
Mass per Unit Area: 4.74 kg/m² (0.97 lbs/ft²)
Calculation Area: 6.655 m² (71.63 ft²)

Test Environment

Room Volume: 291.98 m³
Temperature: 21.1 °C ± 0.1 °C (Requirement: ≥ 10 °C and ≤ 5 °C change)
Relative Humidity: 64.8 % ± 0.4 % (Requirement: ≥ 40 % and ≤ 5 % change)
Barometric Pressure: 99.1 kPa (Requirement not defined)

MOUNTING METHOD

Type E-400 Mounting: The test specimen was mounted with an airspace behind it. The numeral suffix in the designation is the distance in millimeters from the exposed face of the test specimen to the test surface, rounded to the nearest integer multiple of 5. For the purposes of this report, the mounting designation uses the top face of Layer 1 for reference. Perimeter edges of Layer 1 were sealed with metal framing.

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report

Turf Design
2019-02-05

RAL™-A19-046

Page 3 of 8



Figure 1 – Specimen mounted in test chamber



Figure 2 – Detail of specimen materials, typical Switchblade joints

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An  ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report

Turf Design
2019-02-05

RAL™-A19-046

Page 4 of 8

TEST RESULTS

Specimen total absorption and absorption coefficient are tabulated at the eighteen standard frequencies. A graphic presentation of the data and additional information appear on the following pages.

1/3 Octave Center

Frequency (Hz)	Total Absorption (m ²)	Total Absorption (Sabins)	Absorption Coefficient
100	4.08	43.88	0.61
** 125	3.15	33.94	0.47
160	3.38	36.41	0.51
200	3.54	38.12	0.53
** 250	4.16	44.80	0.63
315	4.55	49.00	0.68
400	4.81	51.78	0.72
** 500	5.47	58.87	0.82
630	5.59	60.20	0.84
800	5.72	61.57	0.86
** 1000	6.12	65.89	0.92
1250	6.34	68.20	0.95
1600	6.78	73.01	1.02
** 2000	6.70	72.08	1.01
2500	6.66	71.68	1.00
3150	6.70	72.11	1.01
** 4000	6.70	72.15	1.01
5000	6.64	71.44	1.00

SAA = 0.83

NRC = 0.85

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report

Turf Design
2019-02-05


RAL™-A19-046
Page 5 of 8

TEST RESULTS (continued)

The sound absorption average (SAA) is defined in ASTM C423-17 Section 3.1.1 as the arithmetic average of the sound absorption coefficients of a material for the twelve one-third octave bands from 200 Hz through 2500 Hz, inclusive, rounded to the nearest integer multiple of 0.01.

The noise reduction coefficient (NRC) is defined from previous versions of ASTM C423 as the arithmetic average of the sound absorption coefficients at 250 Hz, 500 Hz, 1000 Hz, and 2000 Hz, rounded to the nearest integer multiple of 0.05.


Tested by


Marc Sciaky
Senior Experimentalist

Report by


Malcolm Kelly
Test Engineer, Acoustician

Approved by


Eric P. Wolfram
Laboratory Manager

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An  ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report


Turf Design
2019-02-05

RAL™-A19-046

Page 6 of 8

SOUND ABSORPTION REPORT

Switchblade C2 over fissured ceiling tiles



SAA = 0.83

NRC = 0.85

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

Test Report

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Turf Design
2019-02-05

RAL™-A19-046

Page 7 of 8

APPENDIX A: Extended Frequency Range Data

Specimen: Switchblade C2 over fissured ceiling tiles (See Full Report)

The following non-accredited data were obtained in accordance with ASTM C423-17, but extend beyond the defined frequency range of 100Hz to 5,000Hz. These unofficial results are representative of the RAL test environment only and intended for research & comparison purposes.

1/3 Octave Band Center Frequency (Hz)	Total Absorption (Sabins)	Absorption Coefficient
31.5	41.56	0.58
40	0.82	0.01
50	24.00	0.34
63	25.29	0.35
80	42.87	0.60
100	43.88	0.61
125	33.94	0.47
160	36.41	0.51
200	38.12	0.53
250	44.80	0.63
315	49.00	0.68
400	51.78	0.72
500	58.87	0.82
630	60.20	0.84
800	61.57	0.86
1000	65.89	0.92
1250	68.20	0.95
1600	73.01	1.02
2000	72.08	1.01
2500	71.68	1.00
3150	72.11	1.01
4000	72.15	1.01
5000	71.44	1.00
6300	75.14	1.05
8000	77.41	1.08
10000	77.53	1.08
12500	85.25	1.19

1512 S BATAVIA AVENUE
GENEVA, IL 60134
630-232-0104

An  ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM

FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report

Turf Design
2019-02-05

RAL™-A19-046

Page 8 of 8

APPENDIX B: Instruments of Traceability

Specimen: Switchblade C2 over fissured ceiling tiles (See Full Report)

<u>Description</u>	<u>Model</u>	<u>Serial Number</u>	<u>Date of Certification</u>	<u>Calibration Due</u>
System 1	Type 3160-A-042	3160-106968	2018-08-09	2019-08-09
Bruel & Kjaer Mic And Preamp A	Type 4943-B-001	2311428	2018-09-28	2019-09-28
Bruel & Kjaer Pistonphone	Type 4228	2781248	2018-08-06	2019-08-06
EXTECH Hygro 662	SD700	A083662	2018-11-29	2019-11-29

APPENDIX C: Revisions to Original Test Report

Specimen: Switchblade C2 over fissured ceiling tiles (See Full Report)

<u>Date</u>	<u>Revision</u>
2019-02-06	Original report issued

END